

August 4th scheduled

Bridge Street - Chip seal.

Comstock Bridge Road - Chip seal

Waterhole Road - Chip Seal. Note there is a section of this road that is the responsibility of the Town of East Hampton for maintenance that will not be conducted.

On Chip Sealed roads, the speed limit is reduced to 15 mph in order to keep the material in place.

Mid-August scheduled

Debi Circle and Diane Lane - Capeseal - This is a two-step process, the first resembles chip seal, and then two weeks after placement, an emulsion is placed over the stone that smooths and seals the surface.

Late August scheduled

Dr Foote Road - Midland to Cabin - Cold in Place Recycled - with overlay to follow in 6 weeks.

Clark Road - Cold in Place Recycled - with overlay to follow in 6 weeks.

Balaban Road - Cold in Place Recycled - with overlay to follow in 6 weeks.

September tentatively scheduled

Old Hartford Road - From Jones Street to Chittenden Road - 2" Milling and Pavement Replacement.