

Request for Proposal
POST TENSION CONCRETE TENNIS COURT PROJECT
AT COLCHESTER RECPLEX
Bid #2022-008
Due AUGUST 10, 2022 at 2:00 p.m.

Addendum 2

The following information has been updated:

1.3 D. Concrete Curbing:

A 12' wide x 12" deep concrete curb shall be installed along all fence lines. Fence lines should be centered in the concrete curb. The finished elevation of the concrete curb shall be at the same elevation as the post tension slab.

1.3 E. Accessories:

New Net Posts, Nets, and Center Straps will be provided and installed for the tennis courts. Net posts should be 3" SQ.

These sections, regarding fencing and perimeter curb, are not applicable as we plan on keeping the existing fence. The existing fence may need to be adjusted to accommodate the new floor elevation.