



360 Captain Lewis Drive  
 Southington CT 06489  
 (P) 860-953-8888 / (F) 860-953-5877  
 CT S1-390692 / CT SM1-2010  
 AA/EOE

11/4/22

Town of Colchester

Re: Town Hall- HVAC upgrades- Budget 22/23'

- ❖ Demo and properly dispose of existing equipment.
- ❖ Furnish and install (19) Daikin high-efficiency WSHP.
- ❖ Furnish and install (3) high-efficiency HP RTU (lower roof) with curb adapters.
- ❖ Furnish and install (1) Evapco closed loop cooling tower- including new VFD and control enclosure.
- ❖ Provide new support steel to accommodate new tower and reconnect to existing piping.
- ❖ Furnish and install new bathroom exhaust fans.
- ❖ Fabricate and install sheet metal transitions for new WSHP.
- ❖ Replace (2) system circulator pumps- B&G EcocircXL 40-275.
- ❖ Furnish and install new 4" air separator and provide 5gal shot feeder for water treatment.
- ❖ Provide line voltage electrical for new equipment.
- ❖ Labor to start and test.
- ❖ Owner training.

Total Cost including labor and material: .....\$ 415,000.00

**Notes/exclusions:**

Exclude: CT sales tax, 2<sup>nd</sup> shift, boilers, burner conversions, water treatment, DDC upgrades and prevailing wage.

Steve Zagurski  
*Steve Zagurski*  
 President  
 Air Temp Mechanical Services  
 360 Captain Lewis Dr  
 Southington, CT 063489  
 Office: (860)953-8888  
 Cell: (860)234-1086

