

Tank Quote

Shawn Stula <shawn@stulallc.com>

Thu 6/16/2022 1:32 PM

To: Steve Sharpe <fleet@colchesterct.gov>

Price and scope of work for removal of existing 10,000 gallon UST located at Colchester town hall \$ 19,650

- Removal and disposal of existing tank with sub contracted environmental service to provide soil testing and closure report. Report to be filed with DEEP by town as required.
- Organize sub contracted company to properly dispose of the tank
- Town to transport, and provide clean, suitable fill as required to fill in tank grave, as well as top soil as required.
- Town will be required to haul in some structural gravel as well in areas where asphalt and concrete sidewalk will be patched.
- Town to have all existing fuel and sludge sucked from the tank and existing piping to low enough levels so that tank can be transported legally to disposal facility
- Price includes patching asphalt that may be disturbed in parking lot, as well as patching any disturbed areas of the sidewalk.
- Price does not include excavation or disposal of any pollution that may be uncovered, as well as any unforeseen things, not marked out by CBYD such as but not limited to buried pipes, wires, tanks, rocks over 24" in any one direction, ledge, buried organic materials, ECT. These will be brought to towns attention and continued on a time and materials basis.
- Any permit fees to be added to final bill with no markup.

-

Price and scope of work for temporary installation of a town provided 1,000 gallon convault tank and tank pad \$ 17,775

- Installation of Town provided 1000 gallon convault tank, and pre cast tank pad.
- Town provided tank to include all tank top items required by code, such as but not limited to gauges, fill ports, emergency vents, interstitial wall monitors ECT.
- Town to provide crane service and transportation of tank and precast pad.
- Stula enterprises to provide site work to prepare site for precast pad and tank and hire sub contracted plumbing company to install temporary piping, above ground into town hall to tie into existing furnace, generator day tank, and water heater under oversight of town building officials, and fire marshal.
- If it is found that existing infrastructure (I.E. pumps, day tanks Ect.) are found to not be suitable to be used with new above ground tank these issues will have to be resolved at that time at possible additional cost.
- Price does not include excavation or disposal of any pollution that may be uncovered, as well as any unforeseen things, not marked out by CBYD such as but not limited to buried pipes, wires, tanks, rocks over 24" in any one direction, ledge, buried organic materials, ECT. These will be brought to towns attention and continued on a time and materials basis.
- Transfer of fuel to new tank to be provided by town.
- Any permit fees to be added to final bill with no markup.

No sales tax included in either of these prices.

Sent from Mail for Windows

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.



Petroleum Contractors Since 1984
CT DAS Prequalified Contractor
Web Site: SSE-INC.Net
Members of NFPA, PEI, CBIA, ICPA
Veeder Root/ Gilbarco ASC

1-800-801-TANK

June 28, 2022

Steve
Town of Colchester DPW/Highway Garage
300 Old Hartford Road
Colchester, CT 06415

Via Email: fleet@colchesterct.gov

RE: Pump Out – Town Hall #2 Oil tank, then redistribute to various town fuel tank locations, remove tank bottom/sludge.

Service Station Equipment, Inc. is pleased to provide you with this quote for the above referenced facility:

- * Vac Truck Fee \$120.00 per hour
- * Manifest fee \$95.00 (Sludge Removal & Disposal per site)
- * Disposal of pumped out fluid \$1.35 per gal (50 Gallon Minimum)

Note: Labor and materials are estimates only and will be billed at actual time and material. Disposal cost will also depend on total gallons removed. Estimate not to exceed \$4500.00

Accepted by: _____ Date: _____

If you have any questions or concerns regarding this quote please contact me directly, 860.848.2278 x 113.

Tanks-A-Lot!

Jaime Lee

Jaime Lee
Administration

****Price quoted is assuming that the product is oil/water with a low level of halogens. If liquids come in at a high halogen level, the price per gallon for disposal will be higher. ****

70 Murphy Road, North Franklin, CT 06254

Page 1 of 1

6 860.848.2278 ~ 1 860.642.8005

CT License # 902338 - CP Plumbing Lic # 202469 - CT Weights & Measures DLR # 106
Oil Spill Card # 9690967 - RI "Gas Station Ltd." Lic. - MA Pipefitter PJ-299751



United Concrete Products
 173 Church St
 Yalesville, CT 06492
 Phone: (800) 234-3119
 Fax: (203) 265-4941

Quote Number: 49955

Quote Date: 6/8/2022

CUSTOMER

Bill to:	COLCHESTER, TOWN OF HIGHWAY DEPT 300 OLD HARTFORD RD COLCHESTER, CT 06415	Project:	TOWN HALL 127 NORWICH AVE. COLCHESTER, CT 06415
Contact:	STEVE SHARPE	Site Contact:	
Phone:		Fax:	
Phone:		Phone:	
Customer ID:	2030-4	ShipVia:	N/A
Terms:	NET 30	PO:	
		Sales Rep:	Gregory Job

Qty	Item	Description	Unit Weight	UOM	Unit Price	Extension
	Structure: 1,000 CONVAULT					
1	CONJ03	CONVAULT BASE SLAB 1000	4,680	EA	\$1,025.00	\$1,025.00
1	CONP01	1000 PLATFORM STAIR SLAB	598	EA	\$110.00	\$110.00
1	CONQ02	TRUCKING & OFFLOADING, RELOCATING EXISTING 1,000 GALLON TANK FROM THE FIREHOUSE TO THE TOWN HALL	1	EA	\$950.00	\$950.00
						\$2,085.00

Total Weight 5,279

Taxable	\$0.00
Non-Taxable	\$2,085.00
Sub Total	\$2,085.00
Tax	\$0.00
Total	\$2,085.00

UNITED CONCRETE PRODUCTS MUST BE INFORMED IF THIS IS A STATE FUNDED PROJECT. THE STATE PROJECT NUMBER MUST BE PROVIDED TO UCP PRIOR TO DELIVERY OF ANY PRODUCT.

THIS QUOTATION IS GOOD FOR ONLY 10 DAYS.

PLEASE NOTE: MATERIAL LEAD TIMES (FROM SUPPLIERS) THAT ARE OUTSIDE OF UNITED CONCRETE'S CONTROL MAY IMPACT DELIVERY LEAD TIMES OF PRODUCT.

ALL PRICING BASED ON APPROVAL OF UCP SUBMITTALS.

.....

Quantities/heights provided are approximations and may vary based on actual field conditions. Billings to reflect actual product produced.

CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL QUANTITIES LISTED ON THIS QUOTATION PRIOR TO ISSUANCE OF PURCHASE ORDER.

INCLUDES:

- * 5000 PSI Type III SCC Concrete
- * Plain Reinforcing (BLACK)

EXCLUDES:

- * Coatings, Sealers, Damproofing
- * Piping
- * Boots, Link Seals, Grout
- * Aluminum Ladder Rungs
- * All Other Materials or Hardware Not Listed On This Quotation

A site check is required to approve off loading with UCP equipment. Because of the tank weight, the truck must be able to get right next to the proposed tank location.



United Concrete Products
 173 Church St
 Yalesville, CT 06492
 Phone: (800) 234-3119
 Fax: (203) 265-4941

Quote Number: 49955

Quote Date: 6/8/2022

CUSTOMER

THIS PROPOSAL DOES NOT INCLUDE PERMITS, SITE PREP, PLUMBING, PIPING, ELECTRONIC MONITORING SYSTEMS, AND/OR ELECTRICAL HOOK UPS AT THE SITE.

** BUOYANCY IS THE RESPONSIBILITY OF THE CONTRACTOR

Please Note:

- Terms and Conditions.
- All pricing based upon approval of UCP submittals.
- United Concrete must receive a valid tax exemption certificate with order or customer will be responsible for any Sales and/or Use Tax amount due on the project.
- Net 30 Days from delivery pending credit approval.
- Retainage is not permitted.
- One Hour Allotted Unloading Time Allowed.

A fee of \$125.00/HR waiting time will be charged beyond one hour if truck is delayed onsite.

Accepted by: _____
(Company)

Accepted by: _____
(Authorize signature)